CLS
EQUIPMENT CO. INC.
www.SewerTools.com

CLS North Service Center
726 S. Sherman Street Richardson, Texas 75081
Office: 972-479-1335 Fax: 972-479-1336
www.sewertools.com

**11/2/2023**

RD Moorman Inc.
ATTN: Matt Fullerton
RE: CUES C550 Unit in Transit 350 Van

**1 FORD TRANSIT GAS CARGO VAN 2X4 CHASSIS**

1 3.5L V6 Gas Engine
1 6-Speed Automatic Transmission
1 10360 lb. GVWR
1 148" Wheel Base
1 Cab Air Conditioner
1 AM / FM Radio
1 Rear View Camera

**2 HIGH INTENSITY LED STROBE SYSTEM - AMBER (REAR OF VEHICLE KICKPLATE / BUMPER)**

**2 HIGH INTENSITY LED STROBE SYSTEM - AMBER (FRONT OF VEHICLE / GRILL AREA)**

**1 TRANSIT VAN EXTERIOR LIGHTING & CONTROL ROOM TO INCLUDE:**

2 LED Amber Beacon
2 Adjustable LED Floodlights Rear of Vehicle Area Illumination

**Control Room Interior:**

1 Lonseal Lonplate Flooring
1 Kemlite Wall & Ceiling Covering
1 Bulkhead Wall With Passage Door From Control Room to Equipment Room
1 Tinted Viewing Window in Bulkhead Wall
1 Tinted Viewing Window in Bulkhead Door
1 Desktop / Work Area
1 LED Light Fixture
2 Electrical Outlet with Dual Receptacles
1 Fire Extinguisher with Bracket, 10BC Rating
1 Operators Chair
1 Breaker Box Storage Area with Locking Positive Latch

**1 CARBON MONOXIDE DETECTOR MOUNTED IN INTERIOR OF UNIT 1**

**COMMAND MODULE MOUNT ON DESKTOP**

**1 TRANSIT VAN EQUIPMENT ROOM INTERIOR TO INCLUDE:**

1 Lonseal Lonplate Flooring
1 Kemlite covered walls and weather resistant/smooth finished ceiling
1 Electrical Outlet with Dual Receptacles
1 LED Light Fixture

CLS North Service Center
726 S. Sherman Street Richardson, Texas 75081
Office: 972-479-1335 Fax: 972-479-1336
www.sewertools.com

**1 SOFT MOUNT AND DROP DOWN/GUIDE ARM/FAIRLEAD SET UP**
- 1 QB082 Mount (R)
- 1 QB306 Mount (F)

**1 1 DRAWER STORAGE BOX FOR UNDER REEL**

**1 CABLE NOTCH UNDER REEL**

**1 22" (MINIMUM) FLATSCREEN COLOR INDUSTRIAL TV MONITOR NTSC / PAL COLOR STANDARDS**

**1 24" REAR FLAT SCREEN MONITOR MOUNTED IN BULKHEAD WALL**
- 1 Flat Screen Monitor
- 1 Cable Assembly - Video Monitor to Monitor in Control Room
- 1 Electrical Outlet

**1 MOUNTING HARDWARE FOR MONITOR to include Bracket(s), and / or Mount(s), and Miscellaneous hardware required to secure monitor for optimal safety and viewing.**

**1 10-GALLON WASHDOWN SYSTEM TO INCLUDE:**
- 1 10-Gallon Fresh Water Tank
- 1 Electric Water Pump
- 1 Retractable Hose Reel with 25' Water Hose and Nozzle

**1 UPPER AND LOWER STORAGE CABINET IN EQUIPMENT ROOM**
- 1 Lower Storage Cabinet / Work Top
- 1 Upper Wall Mounted Storage Cabinet

**1 MULTI-OUTLET WORKSTATION WITH LIGHTS AND USB PORTS INSTALLED IN EQUIPMENT ROOM**

**1 ON-BOARD AC POWER SYSTEM, DYNAMIC INVERTER, 4.5KW**

**1 DIGITAL ENGINEERING PANEL FOR INVERTER SYSTEM, BLACK**

*******FLEXITRAX EQUIPMENT CONFIGURATION*******

**1 C550 FLEXITRAX LARGE DELUXE PACKAGE for 6" to 36" pipe To Include:**
- 1 - C550 Powered Drum A 305m (1000 Ft) Cable W/Swivel
- 1 - Cable Assy Mains P350 USA, NEMA 5-15
- 1 - 6" Tractor Assembly
- 1 - P356 Strap Bracket Kit
- 1 - 4" Tractor Assembly
- 1 - P354 Strap Bracket Kit
- 1 - C550c Command Module
- 1 - C550 Pendant Controller

CLS North Service Center
726 S. Sherman Street Richardson, Texas 75081
Office: 972-479-1335 Fax: 972-479-1336
www.sewertools.com

1- Pan/Tilt Camera
1 - Pan/Tilt Zoom Camera
1 - Fixed Elevator
1 - Large Power Elevator
2 - Medium Wheel Set (No Adaptors Required)
4 - 3" Intermediate Wheels
1 - P350 Wheel Adaptor 238 Hex Set Of 4
2 - Dual Large Pneumatic Wheel Set
1 - Stack Adapter Assy pneumatic Wheels 4-Off
4 - 3" Small Grit Wheel
1 - R W Adaptor P354 65mm Wheel 6" RL
4 - 4" PVC Large Grit Wheel
1 - R W Adaptor P356 105mm Wheel 8" RL
1 - 8W Light Head
1 - Top Roller-Manhole
1 - Downhole Roller- Non-Coated
3 - Pole Extension Aluminum 72"
1 - Tube Adaptor for Downhole Pole
50 - Rope for Cleats
1 - Hook Attachment
1 - 1m Link Cable
1 - Accessory Bag - CUES Grey
1 - Key Ball End Metric Set
1 - 50 mL Grease
1 - C550 Cable Blanking Tow Eye
1 - Mains Lead - USA

Delivery and 3 Days Field Training Included

**Price for CUES C550 on Transit as listed above: $272,427.00**

***Please note that this is a Pre-Built Demo unit and subject to sale at any time***

Regards,

Paul M. Baumy
281-850-1721