

RURAL MUNICIPALITY OF MONET No. 257

Cuckler Straight Wall Building 50' x 80' x 16'

\$37,550.60

WORKSHOP.

1. Heating - Four overhead heaters with a capacity of 960,000 BTU.
2. Sewer and Water - From building edge in - includes 25 gal. water heater.  
Toilet, wash basin, septic tank and jet.
3. Sump in floor - One sump with 48' of floor drain down centre of floor.
4. Doors - Two 14' x 18' overhead doors with chain lifts. Heat cable.  
- Two small walk in doors.
5. Floor - 5" concrete floor reinforced with 3/8 rebar at 18" centres with  
60 lbs. hardner per 100 ft.
6. Metal - 26 gauge metal - Color - Dakota gold - Spray or fibreglass.
7. Electrical - 200 amp. single phase switch and 40 circuit panel.  
35 outlets - 20 florescent lights - five switches and ten plugs.  
4 double outside - one welder plug within 20 ft. of panel.
8. Depth of Piling - 20 x 12.
9. 1 Mercury vapor light at an additional cost of the above tendered price  
-approximately \$135.00
10. Grading and surrounding yard work is to be done by owner.