R14-8
NOV

FOR SALE

2013 CAT 14M Motor Grader

UNIT	HOURS	SERIAL
06-6612	14,813	CAT0014MPN9S00302



UNIT SPECIFICATIONS

Year	**2013**
Make / Model	**CAT 14M**
Unit Number	**06-6612**
Serial Number	**CAT0014MPN9S00302**
Current Hours	**14,813**

CONTACT

Russ Hewson

Director, Corporate Assets
C: 780.908.5938
E: rhewson@mcel.ca

Morgan Construction and Environmental Ltd.
4th Floor, 16901 – 109 Ave NW
Edmonton, AB T5P 4P6
mcel.ca

Inspection by appointment only

01 Major Repair History

1 records • 2024-08-14 – 2024-08-14 • most recent first

Date	Component	Description	Hours	Amount
2024-08-14	Final Drive	Final Drive Parts — Pistons, Plates, Bearings & Springs	9,471	$14,944.06
		Total		**$14,944.06**

02 Hour Meter



Hour Meter — 14,731.5 hrs (at time of photo)

03 Exterior Condition Photos



Front Three-Quarter View



Front Three-Quarter View (Opposite Side)



Rear Three-Quarter View — Ripper

04 Major Component Life Summary

Current Hours: 14,813

Component	Life (hrs)	Last Changed (hrs)	Remaining (hrs)	% Remaining	Status
Air Dryer	10,000	Original	-4,813	-48%	**Past Benchmark**
Alternator	7,000	Original	-7,813	-112%	**Past Benchmark**
Engine	16,000	Original	1,187	7%	Service Soon
Injectors (6)	8,000	Original	-6,813	-85%	**Past Benchmark**
Pump, Water	16,000	Original	1,187	7%	Service Soon
Radiator	16,000	Original	1,187	7%	Service Soon
Starter	8,000	Original	-6,813	-85%	**Past Benchmark**
Turbocharger	9,000	Original	-5,813	-65%	**Past Benchmark**
Axle Assembly, Front	16,000	Original	1,187	7%	**Service Soon**
Brake Group, Front, LHS	16,000	Original	1,187	7%	**Service Soon**
Brake Group, Front, RHS	16,000	Original	1,187	7%	**Service Soon**
Brake Group, Rear, LHS	16,000	Original	1,187	7%	**Service Soon**
Brake Group, Rear, RHS	16,000	Original	1,187	7%	**Service Soon**
Differential	16,000	Original	1,187	7%	**Service Soon**
Final Drive Group, LHS	16,000	Original	1,187	7%	**Service Soon**
Final Drive Group, RHS	16,000	Original	1,187	7%	**Service Soon**
Pump, Brake & Hydraulic Fan	16,000	Original	1,187	7%	**Service Soon**
Pump, Transmission	16,000	Original	1,187	7%	**Service Soon**
Spindle, LHS	16,000	Original	1,187	7%	**Service Soon**
Spindle, RHS	16,000	Original	1,187	7%	**Service Soon**
Transmission	16,000	Original	1,187	7%	**Service Soon**
Cylinder, Articulation, LHS	16,000	Original	1,187	7%	**Service Soon**
Cylinder, Articulation, RHS	16,000	Original	1,187	7%	**Service Soon**
Cylinder, Blade Lift, LHS	16,000	Original	1,187	7%	**Service Soon**
Cylinder, Blade Lift, RHS	16,000	Original	1,187	7%	**Service Soon**

04 Major Component Life Summary continued

Component	Life (hrs)	Last Changed (hrs)	Remaining (hrs)	% Remaining	Status
Cylinder, Blade Tip, LHS	16,000	Original	1,187	7%	Service Soon
Cylinder, Center Shift	14,000	Original	-813	-6%	**Past Benchmark**
Cylinder, Ripper	16,000	Original	1,187	7%	Service Soon
Cylinder, Side Shift	16,000	Original	1,187	7%	Service Soon
Cylinder, Steering, LHS	16,000	Original	1,187	7%	Service Soon
Cylinder, Steering, RHS	14,000	Original	-813	-6%	**Past Benchmark**
Cylinder, Wheel Lean	16,000	Original	1,187	7%	Service Soon
Motor, Fan	16,000	Original	1,187	7%	Service Soon
Pump, Main Hydraulic & Steering	16,000	Original	1,187	7%	Service Soon
Swivel	10,000	Original	-4,813	-48%	**Past Benchmark**
Valve, Main Control	26,000	Original	11,187	43%	Within Life
Blade	16,000	Original	1,187	7%	Service Soon
Drawbar Assembly, Circle	16,000	Original	1,187	7%	Service Soon
Gearbox, Circle Drive	16,000	Original	1,187	7%	Service Soon

Status: Within Life = 20% or more of benchmark life remaining • Service Soon = 0–19% remaining • Past Benchmark = component has exceeded its benchmark life (benchmarks are planning guides, not failure points)

05 Service History

10 most recent services • 2025-11-20 – 2026-09-21 • most recent first

Date	Hour Meter	Service Performed
2026-09-21	14,731	1000-Hour PM Service
2026-09-05	14,518	250-Hour PM Service
2026-08-21	14,230	500-Hour PM Service
2026-08-02	13,926	250-Hour PM Service
2026-07-11	13,629	2000-Hour PM Service
2026-05-25	13,280	250-Hour PM Service
2026-04-29	13,061	500-Hour PM Service
2026-03-25	12,744	250-Hour PM Service
2026-02-13	12,324	1000-Hour PM Service
2025-11-20	12,135	250-Hour PM Service